


Notes:

- Designed to mount Florence Versatile[™] 4C mailbox single column 10-High Suite and ADA Max Height Suite modules (sold separately).
- 2. For use with front loading modules only.

PRODUCT SERIES:	RIES: VERSATILE™ 4C SURFACE MOUNT COLLAR				
		MODEL	SM10S	REV	С
		SCALE	NONE	LAS	T REV DATE 7/03/2014
		DRAWIN	NUMBER		DRAWN BY
			SM10SCS		TNS
		I			

versatile™ 4C Mailbox, 4CADS-01



COMPARTMENT CHART

DESCRIPTION	COMPARTMENT	COMPARTMENT SIZE	QTY.	
MAILBOX	MB2	6-1/2" H x 12" W x 15" D	1	
OUTGOING MAIL	OM2	6-1/2" H x 12" W x 15" D	1	
PARCEL	PL6	20-1/2" H x 12" W x 15" D	1	

Notes:

- 1. This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
 - a. At least one customer compartment shall be positioned less then 48" above finished floor (AFF).
 - b. No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
 - c. No patron (tenant) lock shall be positioned more than 67" AFF.
 - d. No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
 - e. The USPS Arrow lock shall be positioned 36"- 48" AFF.
- 2. This 4C mailbox can also be used for private applications.
- 3. The rough opening width for multi-unit 4C installations is provided using the Florence configurator: www.florencemailboxes.com/configurator.

PRODUCT SERIES: VERSATILETM 4C FRONT LOAD MAILBOX

MODEL 4CADS-01	REV	В	
SCALE NONE	NONE LAST REV DATE 06/29/19		
DRAWING NUMBER	•	DRAWN BY	
4CADS-01CS		RAK	