


versatile™ 4C Mailbox, 7 High Suite



- Notes:
- 1. Below are the USPS STD-4C installation guidelines:
 - a. At least one customer compartment shall be positioned less then 48" above finished floor (AFF).
 - b. No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
 - c. No patron (tenant) lock shall be positioned more than 67" AFF.
 - d. No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
 - e. The USPS Arrow lock shall be positioned 36"- 48" AFF.
 - 2. Modules noted with * do not meet USPS STD-4C guidelines above..
 - 3. The rough opening width for multi-unit 4C installations is provided using the Florence configurator:
www.florencemailboxes.com/configurator.

PRODUCT SERIES: versatile™ 4C Mailbox 7 High Suite

	MODEL	4C7H	REV	B
	SCALE	NONE	LAST REV DATE	08/08/2019
	DRAWING NUMBER	4C7HCS	DRAWN BY	RAK
			SHEET	1 OF 1