



versatile™ 4C Mailbox, 9 High Suite



Floor



Floor

- Notes:
- Below are the USPS STD-4C installation guidelines:
 - At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
 - No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
 - No patron (tenant) lock shall be positioned more than 67" AFF.
 - No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
 - The USPS Arrow lock shall be positioned 36"- 48" AFF.
 - Modules noted with * do not meet USPS STD-4C guidelines above..
 - The rough opening width for multi-unit 4C installations is provided using the Florence configurator:
www.florencemailboxes.com/configurator.

PRODUCT SERIES: versatile™ 4C Mailbox 9 High Suite

	MODEL 4C9H		REV B	
	SCALE NONE		LAST REV DATE 08/08/2019	
	DRAWING NUMBER 4C9HCS		DRAWN BY RAK	SHEET 1 OF 1